

## Tennessee Valley Authority Environmental Quality Protection Specifications for Transmission Substation or Communications Construction

1. **General** – Tennessee Valley Authority (TVA) and/or the assigned contractor and subcontractors shall plan, coordinate, and conduct his or her operations in a manner that protects the quality of the environment and complies with TVA’s environmental expectations discussed in the preconstruction meeting (including clearing and grading or reclearing and removal or dismantling). This specification contains provisions that shall be considered in all TVA and contract construction, dismantling, or forensic operations. If the contractor and his or her subcontractors fail to operate within the intent of these requirements, TVA will direct changes to operating procedures. Continued violation will result in a work suspension until correction or remedial action is taken by the contractor. Penalties and contract termination will be used as appropriate. The costs of complying with the Environmental Quality Protection Specifications are incidental to the contract work, and no additional compensation will be allowed. At all site perimeters, structure, foundation, conduit, grounding, fence, drainage ways, etc., appropriate protective measures to prevent erosion or release of contaminants will be taken immediately upon the end of each step in a construction, dismantling, or forensic sequence, and those protective measures will be inspected and maintained throughout the construction and site stabilization and rehabilitation period.
2. **Regulations** - TVA and/or the assigned contractor and subcontractor(s) shall comply with all applicable federal, state, and local environmental and antipollution laws, regulations, and ordinances related to environmental protection and prevention, control, and abatement of all forms of pollution.
3. **Use Areas** - TVA and/or the assigned contractor and/or subcontractor(s) use areas include but are not limited to site office, shop, maintenance, parking, storage, staging, assembly areas, utility services, and access roads to the use areas. The construction contractor and subcontractor(s) shall submit plans and drawings for their location and development to the TVA engineer and project manager for approval. Secondary containment will be provided for fuel and petroleum product storage pursuant to 29CFR1910.106(D)(6)(iii) (OSHA).
4. **Equipment** - All major equipment and proposed methods of operation shall be subject to the approval of TVA. The use or operation of heavy equipment in areas outside the right-of-way, access routes, site, or structure, pole, or tower sites will not be permitted without permission of the TVA environmental technician or ROW forester. Heavy equipment use on steep slopes (greater than 20 percent) and in wet areas will be held to the minimum necessary to construct the transmission or communication facility. Steps will be taken to limit ground disturbance caused by heavy equipment usage, and erosion and sediment controls will be instituted on disturbed areas in accordance with state requirements and best management practices (BMPs).

No subsurface ground-disturbing equipment or stump-removal equipment will be used by construction forces except on access roads or at the actual site, structure, pole, or tower sites, where only footing locations and controlled runoff diversions shall be created that disturb the

soil. All other areas of ground cover or in-place stumps and roots shall remain in place. (Note: Tracked vehicles disturb surface layer of the ground due to size and function.) Some disking of the right-of-way, access, and site(s) may occur for proper seedbed preparation.

Unless ponding previously occurred (i.e., existing low-lying areas), water should not be allowed to pond on the site or around structures except around foundation holes; the water must be directed away from the site in as dispersed a manner as possible. At tower or structure sites, some means of upslope interruption of potential overland flow and diversion around the footings should be provided as the first step in construction-site preparation. If leveling is necessary, it must be implemented by means that provide for continuous gentle, controlled, overland flow or percolation. A good grass cover, straw, gravel, or other protection of the surface must be maintained. Steps taken to prevent increases in the moisture content of the in-situ soils will be beneficial both during construction and over the service life of any anchor, foundation, or its structure.

5. **Sanitation** - A designated TVA or contractor and/or subcontractor(s) representative shall contract a sanitary contractor who will provide sanitary chemical toilets convenient to all principal points of operation for every working party. The facilities shall comply with applicable federal, state, or local health laws and regulations. They shall not be located closer than 100 feet to any stream or tributary or to any wetland. The facilities shall be required to have proper servicing and maintenance, and the waste disposal contractor shall verify in writing that the waste disposal will be in state-approved facilities. Employees shall be notified of sanitation regulations and shall be required to use the toilet facilities.
6. **Refuse Disposal** - Designated TVA and/or contractor and subcontractor(s) personnel shall be responsible for daily inspection, cleanup, and proper labeling, storage, and disposal of all refuse and debris produced by his or her operations and by his or her employees. Suitable refuse collecting facilities will be required. Only state-approved disposal areas shall be used. Disposal containers such as dumpsters or roll-off containers shall be obtained from a proper waste disposal contractor. Solid, special, construction/demolition, and hazardous wastes as well as scrap are part of the potential refuse generated and must be properly managed with emphasis on reuse, recycle, or possible give away, as appropriate, before they are handled as wastes. Records of the amounts generated shall be provided to the sites or project's designated environmental person. Contractor(s) and subcontractor(s) must meet similar provisions on any project contracted by TVA. Final debris, refuse, product, and material removal is the responsibility of the contractor unless special written agreement is made with the ultimate TVA owner of the site.
7. **Landscape Preservation** - TVA and its contractor(s) and subcontractor(s) shall exercise care to preserve the natural landscape in the entire construction, dismantling, or forensic area as well as use areas, in or outside the right-of-way, and on or adjacent to access roads. Construction operations shall be conducted to prevent any unnecessary destruction, scarring, or defacing of the natural vegetation and surroundings in the vicinity of the work.

8. **Sensitive Areas Preservation** - Certain areas on site and along the access and/or right-of-way may be designated by the specifications or TVA personnel as environmentally sensitive. These areas include but are not limited to areas classified as erodible, geologically sensitive, scenic, historical and archaeological, fish and wildlife refuges, endangered species' habitat, water supply watersheds, and public recreational areas such as parks and monuments. Contractors, their subcontractor(s), and TVA construction crews shall take all necessary actions to avoid adverse impacts to these sensitive areas and their adjacent buffer zones. These actions may include suspension of work or change of operations during periods of rain or heavy public use; hours may be restricted, or concentrations of noisy equipment may have to be dispersed. If prehistoric or historic artifacts or features are encountered during clearing, grading, borrow, fill, construction, dismantling, or forensic operations, the operations shall immediately cease for at least 100 feet in each direction, and TVA's construction superintendent, project manager, project environmental person, and TVA Cultural Resources Program shall be notified. The site shall be left as found until a significance determination is made. Work may continue elsewhere beyond the 100-foot perimeter.
9. **Water Quality Control** - TVA and contractor construction, dismantling, or forensic activities shall be performed by methods that will prevent entrance or accidental spillage of solid matter, contaminants, debris, and other objectionable pollutants and wastes into flowing caves, sinkholes, streams, dry watercourses, lakes, ponds, and underground water sources.

The clearing contractor erected erosion and/or sedimentation control shall be maintained and (when TVA or contract construction personnel are unable) the construction crew(s) shall maintain BMPs such as silt fences on steep slopes and adjacent to any stream, wetland, or other water body. Additional BMPs may be required for areas of disturbance created by construction activities and at sequential steps of construction at the same location on site. BMPs will be inspected by the TVA ROW forester or other designated TVA or contractor and/or subcontractor(s) personnel routinely and during periods of high runoff, and any necessary repairs will be made as soon as practicable. BMP inspections and any required sampling will be conducted in accordance with permit requirements. Records of all inspections and sampling results will be maintained on site, and copies of inspection forms and sampling results will be forwarded to the TVA project manager or project environmental person.

Acceptable measures for disposal of waste oil from vehicles and equipment shall be followed. No waste oil shall be disposed of within the site, access, or right-of-way, on a related construction site or its access roads.

10. **Turbidity and Blocking of Streams** - Construction, dismantling, or forensic activities in or near streamside management zones or other bodies of water shall be controlled to prevent the water turbidity from exceeding state or local water quality standards for that stream. **All conditions** of a general storm water permit, aquatic resource alteration permit, or a site-specific permit **shall be met** including monitoring of turbidity in receiving streams and/or storm water discharges and implementation of appropriate erosion and sediment control measures.

Appropriate drainage facilities for temporary construction, dismantling, or forensic activities interrupting natural site drainage shall be provided to avoid erosion. Watercourses shall not be blocked or diverted unless required by the specifications or the TVA engineer. Diversions shall be made in accordance with TVA's A Guide for Environmental Protection and Best Management Practices for Tennessee Valley Authority Construction and Maintenance Activities (TVA, 2022).

On rights-of-way, mechanized equipment shall not be operated in flowing or standing water bodies except when approved and then, only to construct crossings or to perform required construction under direct guidance of TVA. Construction of stream fords or other crossings will only be permitted at approved locations and to current TVA construction access road standards. Material shall not be deposited in watercourses, their adjacent wetlands, or within stream bank areas where it could be washed away by high stream flows. Appropriate U.S. Army Corps of Engineers' and state permits shall be obtained.

Mechanized equipment shall not be operated in flowing or standing water on substation, switching station, or telecommunication sites.

Wastewater from construction, dismantling, or dewatering operations shall be controlled to prevent excessive erosion or turbidity in a stream, wetland, lake, pond or conveyed to a sinkhole. Any work or placing of equipment within a flowing or dry watercourse requires the prior approval of TVA.

11. **Floodplain Evaluation** - During the planning and design phase of the substation or communications facility, floodplain information should be obtained to avoid locating flood-damageable facilities in the 100-year floodplain. If the preferred site is located within a floodplain area, alternative sites must be evaluated, and documentation prepared to support a determination of "no practicable alternative" to siting in the floodplain. In addition, steps taken to minimize adverse floodplain impacts should also be documented.
12. **Clearing** - No construction, dismantling, or forensic activities may clear additional site or right-of-way vegetation or disturb remaining retained vegetation, stumps, or regrowth at locations other than the structure, substation, or communication site or access thereto. TVA and the construction, dismantling, or forensic contractor(s) must provide appropriate erosion or sediment controls for areas they have disturbed after each disturbance that have previously been restabilized after clearing operations. Control measures shall be implemented as soon as practicable after disturbance in accordance with applicable federal, state, and/or local storm water regulations.

13. **Restoration of Site** - All construction, dismantling, or forensic-related disturbed areas except for farmland under cultivation and any other areas as may be designated by TVA's specifications shall be stabilized in the following manner unless the property owner and permit preparer specify a different method:
  - A. The subsoil shall be loosened to a minimum depth of 6 inches if possible and worked to remove unnatural ridges and depressions.
  - B. If needed, appropriate soil amendments will be added.
  - C. All disturbed areas will initially be seeded with a temporary ground cover such as winter wheat, rye, or millet, depending on the season. Perennials may also be planted during initial seeding if proper growing conditions exist. Final restoration and final seeding will be performed as line construction is completed. Final seeding will consist of permanent perennial grasses such as those outlined in TVA's A Guide for Environmental Protection and Best Management Practices for Tennessee Valley Authority Construction and Maintenance Activities (TVA, 2022). Exceptions would include those areas designated as native grass planting areas. Initial and final restoration will be performed by the clearing contractor.
  - D. Rehabilitation species shall use species designated by federal guidance that are low-maintenance, native species appropriate for the site conditions that prevail at that location.
  - E. TVA holds the option, depending upon the time of year and weather condition, to delay or withdraw the requirement of seeding until more favorable planting conditions are certain. In the meantime, other stabilization techniques must be applied.
  - F. The site must be protected from species designated by the federal Invasive Species Council and must not be the source of species that can be transported to other locations via equipment contaminated with viable materials; thus, the equipment must be inspected, and any such species' material found must be removed and destroyed prior to transport to another location.
14. **Air Quality Control** - Construction, dismantling, and/or forensic crews shall take appropriate actions to minimize the amount of air pollution created by their operations. All operations must be conducted in a manner that avoids creating a nuisance and prevents damage to lands, crops, dwellings, or persons.
15. **Burning** - Before conducting any open burning operations, the contractor and subcontractor(s) shall obtain permits or provide notifications as required to state forestry offices and/or local fire departments. Burning operations must comply with the requirements of state and local air pollution control and fire authorities and will only be allowed in approved locations and during appropriate hours and weather conditions. If weather conditions such as wind direction or speed change rapidly, the contractor's burning operations may be temporarily stopped by the

TVA ROW forester. The debris for burning shall be piled and shall be kept as clean and as dry as possible, then burned in such a manner as to reduce smoke. No materials other than dry wood shall be open burned. The ash and debris shall be buried away from streams or other water sources and shall be in areas coordinated with the property owner on rights-of-way or project manager for TVA sites.

**16. RENOVATION OR DEMOLITION DEBRIS MAY NOT BE BURNED.**

17. **Dust and Mud Control** - Construction, dismantling, or forensic activities shall be conducted to minimize the creation of dust. This may require limitations as to types of equipment, allowable speeds, and routes utilized. Water, straw, wood chips, dust palliative, gravel, combinations of these, or similar control measures may be used subject to TVA's approval. On new construction sites and easements, the last 100 feet before an access road approaches a county road or highway shall be graveled to prevent transfer of mud onto the public road.
18. **Vehicle Exhaust Emissions** - TVA and/or the contractor(s) and subcontractor(s) shall maintain and operate equipment to limit vehicle exhaust emissions. Equipment and vehicles that show excessive emissions of exhaust gasses and particulates due to poor engine adjustments or other inefficient operating conditions shall not be operated until corrective repairs or adjustments are made.
19. **Vehicle Servicing** - Routine maintenance of personal vehicles will not be performed on the right-of-way or access route to the site. However, if emergency or "have to" situations arise, minimal/temporary maintenance to personal vehicles will occur in order to mobilize the vehicle to an off-site maintenance shop. Heavy equipment will be serviced on the site except adjacent to or in designated sensitive areas. The Heavy Equipment Department within TVA or the construction, dismantling, or forensic contractor will properly maintain these vehicles with approved spill protection controls and countermeasures. If emergency maintenance in a sensitive or questionable area arises, the project environmental person will be consulted. All wastes and used oils will be properly recovered, handled, and disposed/recycled. Records of amounts generated shall be provided to TVA. Equipment shall not be temporarily stored in stream floodplains whether overnight or on weekends or holidays.
20. **Smoke and Odors** - TVA and/or the contractor(s) and subcontractor(s) shall properly store and handle combustible material that could create objectionable smoke, odors, or fumes. The contractor and subcontractor(s) shall not burn refuse such as trash, rags, tires, plastics, or other debris.
21. **Noise Control** - TVA and/or the contractor and subcontractor(s) shall take measures to avoid the creation of noise levels that are considered nuisances, safety, or health hazards. Critical areas including but not limited to residential areas, parks, public use areas, and some ranching operations will require special considerations. TVA's criteria for determining corrective measures shall be determined by comparing the noise level of the construction, dismantling, or forensic operation to the background noise levels. In addition, especially noisy equipment such

as helicopters, pile drivers, air hammers, chippers, chain saws, or areas for machine shops, staging, assembly, or blasting may require corrective actions when required by TVA.

22. **Noise Suppression** - All internal combustion engines shall be properly equipped with mufflers as required by the Department of Labor's Safety and Health Regulations for Construction. TVA may require spark arresters in addition to mufflers on some engines. Air compressors and other noisy equipment may require sound-reducing enclosures in some circumstances.
23. **Damages** - The movement of construction, dismantling, or forensic crews and equipment shall be conducted in a manner that causes as little intrusion and damage as possible to crops, orchards, woods, wetlands, and other property features and vegetation. The contractor and subcontractor(s) will be responsible for erosion damage caused by his or her actions and employees and, especially, for creating conditions that would threaten the stability of the right-of-way or site soil, the structures, or access to either. When property owners prefer the correction of ground cover condition or soil and subsoil problems themselves, the section of the project to be handled shall be documented with an implementation schedule and a property owner signature obtained.
24. **Final Site Cleanup and Inspection** - The contractor's designated person shall ensure that all construction, dismantling, or forensic-related debris, products, materials, and wastes are properly handled, labeled as required, and removed from the site. Upon completion of those activities, that person and a TVA-designated person shall walk down the site and complete an approval inspection.

## References

Tennessee Valley Authority. 2022. *A Guide for Environmental Protection and Best Management Practices for Tennessee Valley Authority Construction and Maintenance Activities, Revision 4*. Edited by S.T. Benefield, R.L. Brannon, J.C. Buttram, B.V. Dalton, G.D. Dalton, C.A. Henley, W.G. Martin, A.E. Masters, C.L. Phillips, C.A. Suttles, and R.C. Wilson. Chattanooga, TN. Retrieved from <<https://www.tva.com/Energy/Transmission-System/Transmission-System-Projects>> (n.d.).

Revised August 2022